PACKAGE 1 OF 2

Solar PV + Solis String Inverter (No Backup)

On-grid solar under Solar ATAP. Jinko Tiger Neo N-type 635 W panels with a Solis string inverter, sized to the array. No battery and no backup.

No. of panels	System size	Package price	Potential saving†
12 panels	7.62 kWp	**RM 22,300**	RM 209 /mo
14 panels	8.89 kWp	**RM 24,400**	RM 244 /mo
16 panels	10.16 kWp	**RM 26,100**	RM 279 /mo
18 panels	11.43 kWp	**RM 28,000**	RM 314 /mo
20 panels	12.70 kWp	**RM 29,900**	RM 349 /mo
22 panels	13.97 kWp	**RM 31,800**	RM 384 /mo
24 panels	15.24 kWp	**RM 33,600**	RM 418 /mo
26 panels	16.51 kWp	**RM 35,800**	RM 453 /mo
28 panels	17.78 kWp	**RM 37,700**	RM 616 /mo
30 panels	19.05 kWp	**RM 39,600**	RM 660 /mo
32 panels	20.32 kWp	**RM 40,600**	RM 704 /mo
34 panels	21.59 kWp	**RM 43,200**	RM 748 /mo
36 panels	22.86 kWp	**RM 45,100**	RM 792 /mo

Notes

- Prices are in Ringgit Malaysia per complete installed system: panels, inverter, mounting, cabling, installation, SEDA registration fee and TNB endorsement.
- 12-panel systems are single-phase; systems of 14 panels and above are 3-phase.
- The SuRIA Home rebate of up to RM 3,000 is claimed after commissioning and is not deducted from the package price. It is available until 31 Dec 2026, subject to eligibility.
- †Potential saving is an estimate: 90 kWh per kWp per month (3.15 peak sun hours). 20% is used at home during the day at RM 0.4443/kWh, and 80% is exported under Solar ATAP at RM 0.2703/kWh (RM 0.3703/kWh once generation reaches 1,500 kWh a month). Actual saving depends on household usage and tariff.
- The final price is confirmed after a site survey. Roof works and optional add-ons are quoted separately.

PACKAGE 2 OF 2

Solar PV + GoodWe Hybrid + Battery (No Backup)

Hybrid solar with battery storage sized to the array. Jinko Tiger Neo N-type 635 W panels, a GoodWe hybrid inverter and GoodWe Lynx A G4 16 kWh battery modules. No backup.

No. of panels	System size	Battery	Package price	Potential saving†
12 panels	7.62 kWp	16 kWh	**RM 35,800**	**RM 305** /mo
14 panels	8.89 kWp	16 kWh	**RM 41,200**	**RM 355** /mo
16 panels	10.16 kWp	32 kWh	**RM 54,300**	**RM 406** /mo
18 panels	11.43 kWp	32 kWh	**RM 56,100**	**RM 457** /mo
20 panels	12.70 kWp	32 kWh	**RM 58,200**	**RM 508** /mo
22 panels	13.97 kWp	32 kWh	**RM 60,000**	**RM 559** /mo
24 panels	15.24 kWp	32 kWh	**RM 61,900**	**RM 609** /mo
26 panels	16.51 kWp	32 kWh	**RM 64,200**	**RM 660** /mo
28 panels	17.78 kWp	32 kWh	**RM 66,100**	**RM 864** /mo
30 panels	19.05 kWp	32 kWh	**RM 68,800**	**RM 926** /mo
32 panels	20.32 kWp	48 kWh	**RM 81,100**	**RM 988** /mo
34 panels	21.59 kWp	48 kWh	**RM 83,700**	**RM 1,049** /mo
36 panels	22.86 kWp	48 kWh	**RM 85,600**	**RM 1,111** /mo

Notes

- Prices are in Ringgit Malaysia per complete installed system: panels, inverter, battery modules, mounting, cabling, installation, SEDA registration fee and TNB endorsement.
- Battery sized to the system: 16 kWh (1 module) for 12–14 panels, 32 kWh (2 modules) for 16–30 panels and 48 kWh (3 modules) for 32–36 panels.
- No backup: the battery stores daytime solar for evening use, but the home is not powered during a TNB outage. **Backup add-on: RM 3,200 per system**, if required.
- 12-panel systems are single-phase; systems of 14 panels and above are 3-phase.
- The SuRIA Home rebate of up to RM 3,000 is claimed after commissioning and is not deducted from the package price. It is available until 31 Dec 2026, subject to eligibility.
- †Potential saving is an estimate: 90 kWh per kWp per month (3.15 peak sun hours). Solar is used at home during the day and stored in the battery for the evening, valued at RM 0.4443/kWh (RM 0.54/kWh once generation reaches 1,500 kWh a month). Actual saving depends on household usage and tariff.
- The final price is confirmed after a site survey. Roof works and optional add-ons are quoted separately.